

PROFESSIONAL PRE-DELIVERY INSPECTION (PDI) GUIDELINE & CHECKSHEET

Gujarat, India | Universal Vehicle Inspection Manual

Document Purpose

This is a comprehensive Pre-Delivery Inspection (PDI) guideline and checklist designed by a 15-year industry expert, incorporating best practices from India's leading PDI service providers including Zekardo (3700+ checkpoints), CarVaidya (360° assessment), Cars24, PDI Boss (3500+ checkpoints), and Team-BHP community standards.

Applicable for: All cars regardless of fuel type (Petrol/Diesel/CNG/EV/Hybrid), transmission (Manual/Automatic/AMT/DCT/CVT), body type (Hatchback/Sedan/SUV/Crossover/MUV), brand, variant, or price segment.

HOW TO USE THIS CHECKSHEET

Preparation Guidelines

- Timing:** Conduct PDI 1 day before delivery in broad daylight (10 AM - 4 PM)
- Location:** Open, well-lit area with space to walk around vehicle
- Duration:** Allocate 90-120 minutes minimum
- Team:** Bring 2-3 people to cross-verify observations
- Tools Required:**
 - Paint thickness meter (optional but recommended)
 - Smartphone with OBD2 scanner app
 - OBD2 Bluetooth adapter (ELM327 or similar)
 - Flashlight/torch
 - Measuring tape

- o This printed checksheet
- o Camera/phone for photo documentation

Observation Methods

- **VISUAL:** Look carefully at condition, alignment, color, cleanliness
- **TOUCH:** Feel for smoothness, vibrations, temperature, fitment
- **HEARING:** Listen for unusual sounds, rattles, squeaks
- **OPERATION:** Test every button, switch, lever, and function
- **SMELL:** Detect unusual odors (chemical, burning, musty)
- **MEASUREMENT:** Use tools for precise verification

Rating System

For each checkpoint, mark one of the following:

Rating	Symbol	Meaning	Action Required
PASS	✓	Perfect condition, works as expected	None
MINOR	△	Small issue, cosmetic defect	Note for dealer fixing
MAJOR	×	Serious defect, safety concern	Must fix or reject vehicle
N/A	—	Not applicable to this vehicle variant	Skip this point

Photo Documentation: Take photos of ANY issue marked as MINOR or MAJOR

SECTION 1: DOCUMENTATION VERIFICATION

Inspect **BEFORE** starting physical inspection

#	Checkpoint	Method	Rating	Remarks
1.1	Sales invoice with correct name, amount, vehicle details	Visual		
1.2	Engine number matches invoice and physical engraving	Visual		Engine Bay: _____ Invoice: _____
1.3	Chassis/VIN number matches invoice and physical stamping	Visual		Dashboard: _____ Door Pillar: _____ Invoice: _____
1.4	Registration Certificate (RC) or Temporary Registration	Visual		Name spelling correct? ☐ Yes ☐ No
1.5	Insurance policy - name, vehicle details, validity dates	Visual		Valid from: _____ to: _____
1.6	PUC (Pollution Under Control) certificate - valid 1 year	Visual		Valid till: _____

#	Checkpoint	Method	Rating	Remarks
1.7	Warranty booklet with dealer stamps and signatures	Visual		Warranty period: _____ years/km
1.8	Owner's manual in requested language	Visual		Language: _____
1.9	Service booklet/service schedule booklet	Visual		
1.10	Extended warranty papers (if purchased)	Visual		
1.11	Payment receipts - all installments/full payment	Visual		Total paid: ₹_____
1.12	Accessories warranty cards (battery, tyres, infotainment)	Visual		Battery: __yr Tyres: __yr
1.13	Roadside assistance card/contact details	Visual		Valid for: _____ years
1.14	FASTag receipt/sticker (if applicable)	Visual		Activated? ☐ Yes ☐ No
1.15	CNG/Bi-fuel certificate (for CNG vehicles)	Visual		
1.16	All payment agreement terms match invoice	Visual		

Documentation Photo: Click photo of all documents together

SECTION 2: EXTERIOR BODY & PAINT INSPECTION

Condition: Inspect in broad daylight. Check from 3 feet distance and arm's length.

2A: Paint & Body Panels

#	Checkpoint	Method	Rating	Remarks
2.1	Paint finish - uniform shine, no orange peel texture	Visual		
2.2	Color consistency across all panels (bonnet, doors, fenders, bumpers)	Visual		Check side-by-side comparison Bonnet:____ Door:____ Fender:____ Bumper:____
2.3	Paint thickness check with meter (if available) - 100-180 microns factory standard	Measurement		
2.4	No scratches on bonnet, roof, boot, all doors	Visual/Touch		
2.5	No dents or depressions anywhere on body	Visual/Touch		

#	Checkpoint	Method	Rating	Remarks
2.6	No ripples or waves in paint (indicates repainting)	Visual		Check at angle in sunlight
2.7	Panel gaps uniform - bonnet to fender, door to body, boot to panel	Visual/Measurement		4-6mm is normal
2.8	Panel alignment - all doors, bonnet, boot flush with body	Visual		No high/low edges
2.9	No overspray marks or paint runs	Visual		Check edges and door jambs
2.10	Bonnet opens/closes smoothly, latches securely	Operation		
2.11	Bonnet hydraulic struts hold bonnet open without support	Operation		No sagging? ☐ Yes ☐ No
2.12	Boot/tailgate opens/closes smoothly, latches securely	Operation		
2.13	Boot hydraulic struts functional (if equipped)	Operation		
2.14	All 4 doors open/close smoothly with proper sound	Operation		Driver:____ Pass:____ RL:____ RR:____
2.15	Door hinges properly aligned, no resistance	Operation		
2.16	Door check mechanism works (holds door at positions)	Operation		
2.17	Fuel filler door opens smoothly, spring-loaded (if applicable)	Operation		
2.18	Fuel cap present, threads clean, seals properly	Visual/Operation		

2B: Glass & Transparency

#	Checkpoint	Method	Rating	Remarks
2.19	Windshield - no cracks, chips, scratches	Visual		
2.20	Rear windshield - perfect condition	Visual		
2.21	All door glasses - no defects	Visual		
2.22	Quarter glasses - clean and defect-free	Visual		
2.23	Sunroof/panoramic glass - no scratches (if equipped)	Visual		
2.24	Rear windshield defogger lines intact	Visual		
2.25	VIN sticker on windshield readable	Visual		
2.26	No manufacturing dates/stickers left on glass	Visual		

2C: Lights & Visibility

#	Checkpoint	Method	Rating	Remarks
2.27	Headlights - both working on low beam	Operation		Left:___ Right:___
2.28	Headlights - both working on high beam	Operation		
2.29	Fog lights - front both working (if equipped)	Operation		
2.30	Fog light - rear working (if equipped)	Operation		
2.31	DRLs (Daytime Running Lights) working (if equipped)	Operation		
2.32	Cornering lights working (if equipped)	Operation		
2.33	LED headlight pattern correct, no dead LEDs	Visual		
2.34	Tail lights - both working	Operation		
2.35	Brake lights - all working when brake pressed	Operation		
2.36	Turn indicators - all 4 corners working with correct flash rate	Operation		FR:___ FL:___ RR:___ RL:___
2.37	Side repeater indicators working (on mirrors/fenders)	Operation		
2.38	Reverse lights - working when in reverse gear	Operation		
2.39	Number plate lights - working	Operation		Front:___ Rear:___
2.40	Puddle lamps working (if equipped)	Operation		
2.41	Welcome/approach lights working (if equipped)	Operation		
2.42	Headlight alignment - both pointing same direction	Visual		Test on wall at night
2.43	Lens clarity - no condensation inside any light cluster	Visual		

2D: Mirrors & External Features

#	Checkpoint	Method	Rating	Remarks
2.44	ORVMs (side mirrors) - no scratches on glass	Visual		
2.45	ORVM housings - no damage, paint matching body	Visual		
2.46	ORVM electric adjustment working in all directions	Operation		Left:___ Right:___
2.47	ORVM folding - manual or electric working	Operation		Fold/Unfold smooth
2.48	ORVM auto-fold on lock/unlock working (if equipped)	Operation		
2.49	ORVM turn indicators working (if equipped)	Operation		
2.50	ORVM heating function working (if equipped)	Operation		
2.51	ORVM auto-dimming working (if equipped)	Operation		
2.52	Door handles - exterior finish perfect, no scratches	Visual		All 4 doors + boot
2.53	Chrome/silver trim pieces properly fitted	Visual/Touch		No loose edges
2.54	Body cladding properly fitted (if equipped)	Visual/Touch		Check for gaps
2.55	Roof rails fitted securely (if equipped)	Visual/Touch		No movement

#	Checkpoint	Method	Rating	Remarks
2.56	Sunroof/panoramic roof glass clean, no scratches	Visual		
2.57	Sunroof operates smoothly - tilt and slide	Operation		No jerks/noise
2.58	Sunroof closes completely, no gaps	Operation/Visual		Pour water test if allowed
2.59	Sunroof sunshade operates smoothly	Operation		
2.60	Antenna present and properly fitted	Visual		Shark fin/rod type
2.61	Roof-mounted spoiler fitted properly (if equipped)	Visual		

2E: Underbody & Ground Clearance

#	Checkpoint	Method	Rating	Remarks
2.62	Vehicle sits level - no tilt to any side	Visual		Use level ground
2.63	Ground clearance appears normal for variant	Visual/Measurement		Measure if possible: __mm
2.64	Underbody trays/splash guards fitted properly	Visual		Use phone camera from below
2.65	No visible oil leaks from engine/transmission	Visual		Look for wet spots
2.66	Exhaust pipe properly fitted, no damage	Visual		
2.67	Exhaust hangers secure, no rattles when pushed	Touch/Hearing		
2.68	Silencer/muffler in good condition	Visual		No rust/dents
2.69	Catalytic converter fitted (for BS6 vehicles)	Visual		
2.70	No loose wires hanging underneath	Visual		
2.71	Fuel tank underbody shield fitted (if equipped)	Visual		

2F: Rubber & Seals

#	Checkpoint	Method	Rating	Remarks
2.72	Door rubber seals intact, no tears	Visual/Touch		All 4 doors
2.73	Door seals properly fitted in channels	Visual		No loose sections
2.74	Bonnet rubber seal intact	Visual/Touch		
2.75	Boot rubber seal intact	Visual/Touch		
2.76	Window seals intact around glass	Visual		
2.77	Sunroof drain tubes clear (if equipped)	Operation		Ask dealer to verify

SECTION 3: TYRES & WHEELS

3A: Tyre Inspection

#	Checkpoint	Method	Rating	Remarks
3.1	All 4 tyres same brand as per variant specification	Visual		Brand: _____
3.2	All 4 tyres same size as per variant specification	Visual		Size: _____
3.3	All 4 tyres same model/pattern	Visual		Pattern: _____
3.4	Tyre manufacturing date - within last 6 months	Visual		FL: _____ FR: _____ RL: _____ RR: _____
3.5	How to read: DOT code last 4 digits (WWYY format) - First 2 = Week, Last 2 = Year	Visual		Example: 2024 = 20th week of 2024
3.6	Tread depth uniform across all tyres	Visual/Measurement		Should be 7-8mm for new
3.7	No cuts, bulges, or sidewall damage	Visual/Touch		Check entire circumference
3.8	No manufacturing defects or mold marks	Visual		
3.9	Tyre pressure as per manufacturer specification	Measurement		FL: __ FR: __ RL: __ RR: __ (Spec: __psi)
3.10	TPMS (Tyre Pressure Monitoring System) working (if equipped)	Operation		Shows all 4 pressures
3.11	Spare tyre - same specifications as main tyres	Visual		
3.12	Spare tyre manufacturing date acceptable	Visual		Date: _____
3.13	Spare tyre pressure correct	Measurement		__psi (Usually higher)
3.14	No rubber nipples on tyres (manufacturing artifacts)	Visual		Trim if present

3B: Wheels & Alignment

#	Checkpoint	Method	Rating	Remarks
3.15	All 4 wheels same design as per variant	Visual		
3.16	Wheel size matches specification	Visual		Size: __ inches
3.17	No scratches, dents, or bends on rims	Visual		Check all 4 carefully
3.18	Wheel finish perfect - no paint defects	Visual		Alloy/Steel type
3.19	All wheel center caps fitted properly	Visual		
3.20	Lug nuts/bolts - all present and properly tightened	Visual/Touch		Count: 4 or 5 per wheel

#	Checkpoint	Method	Rating	Remarks
3.21	No rust on wheel hub or brake disc visible	Visual		Light surface rust OK
3.22	Wheels balanced (dealer should confirm)	Operation		Ask for balance report
3.23	Wheel alignment done (dealer should confirm)	Operation		Ask for alignment report
3.24	Vehicle tracks straight when driven	Operation		During test drive

3C: Wheel Accessories

#	Checkpoint	Method	Rating	Remarks
3.25	Jack present in tool kit	Visual		Type: _____
3.26	Wheel brace/spanner present	Visual		
3.27	Tool kit complete with all items	Visual		List items: _____
3.28	Wheel lock key present (if alloy wheels)	Visual		Keep safely!
3.29	Tyre inflator/puncture repair kit (if no spare)	Visual		Check expiry date

SECTION 4: INTERIOR INSPECTION

Spend maximum time here - most features inside

4A: Seats & Upholstery

#	Checkpoint	Method	Rating	Remarks
4.1	Front seats - no stains, tears, or damages	Visual		Driver + Passenger
4.2	Rear seats - perfect upholstery condition	Visual		All seating positions
4.3	Seat stitching uniform, no loose threads	Visual		Check seams
4.4	Seat foam firmness consistent	Touch		Sit and feel
4.5	Headrests fitted on all seats	Visual		Adjust to check
4.6	Driver seat manual adjustment - forward/backward	Operation		Smooth movement
4.7	Driver seat height adjustment (if equipped)	Operation		Up/down smooth
4.8	Driver seat backrest recline adjustment	Operation		Multiple positions
4.9	Driver seat lumbar support (if equipped)	Operation		Inflates/deflates
4.10	Driver seat electric adjustment working (if equipped)	Operation		All directions
4.11	Driver seat memory function (if equipped)	Operation		Save/recall position
4.12	Passenger seat adjustments working	Operation		As applicable
4.13	Rear seat split folding mechanism (if equipped)	Operation		60:40 or 40:20:40
4.14	Rear seat recline working (if equipped)	Operation		

#	Checkpoint	Method	Rating	Remarks
4.15	Third-row seats access easy (if 7/8-seater)	Operation		
4.16	Third-row seats fold/unfold properly (if equipped)	Operation		
4.17	Seat covers fitted properly (if dealer-installed)	Visual		No wrinkles

4B: Seatbelts & Safety

#	Checkpoint	Method	Rating	Remarks
4.18	All seatbelts present (as per seating capacity)	Visual		Count: _____
4.19	Seatbelts - no cuts, fraying, or damage	Visual		Check entire length
4.20	Seatbelts lock when pulled quickly	Operation		Test all positions
4.21	Seatbelts retract smoothly	Operation		No sticking
4.22	Seatbelt buckles lock/unlock properly	Operation		Click sound audible
4.23	Driver seatbelt reminder working	Operation		Beep + dashboard warning
4.24	Passenger seatbelt reminder (if equipped)	Operation		
4.25	Rear seatbelt reminder (if equipped)	Operation		
4.26	Child seat anchor points (ISOFIX) present	Visual		Rear seats
4.27	Airbag labels visible on dashboard/seats	Visual		Do not remove stickers
4.28	Airbag warning light functions (lights up on ignition, goes off)	Operation		Critical safety check

4C: Dashboard & Controls

#	Checkpoint	Method	Rating	Remarks
4.29	Dashboard finish perfect - no scratches	Visual		
4.30	Dashboard padding quality consistent	Touch		Soft-touch areas
4.31	Instrument cluster display working	Operation		All segments visible
4.32	Instrument cluster brightness adjustment	Operation		Dim/bright levels
4.33	MID (Multi-Information Display) working	Operation		Cycle through menus
4.34	Speedometer needle movement smooth	Operation		During test drive
4.35	Tachometer needle movement smooth (if applicable)	Operation		During test drive
4.36	Fuel gauge shows correct level	Visual		Should be full/near full
4.37	Temperature gauge working	Operation		After engine warms up
4.38	Odometer reading under 100 km	Visual		Record: _____ km
4.39	Trip meters reset working	Operation		Trip A & B
4.40	Digital display language correct	Operation		Change if needed

#	Checkpoint	Method	Rating	Remarks
4.41	Warning lights function during ignition	Operation		All light up briefly
4.42	No warning lights stay on after engine start	Operation		All should go off
4.43	Steering wheel - no scratches on rim	Visual/Touch		Leather/urethane check
4.44	Steering wheel tilt adjustment working	Operation		Up/down movement
4.45	Steering wheel telescopic adjustment (if equipped)	Operation		In/out movement
4.46	Steering-mounted controls - all buttons working	Operation		Audio, phone, cruise, ADAS
4.47	Steering paddle shifters working (if equipped)	Operation		Both sides responsive
4.48	Horn working properly	Operation		Clear sound

4D: Center Console & Storage

#	Checkpoint	Method	Rating	Remarks
4.49	Center console finish perfect	Visual		
4.50	Glove box opens/closes smoothly	Operation		Lock working (if equipped)
4.51	Glove box light working (if equipped)	Operation		
4.52	Glove box cooling vent (if equipped)	Operation		Feel airflow
4.53	Center armrest storage opens smoothly	Operation		
4.54	Cupholders present as per specification	Visual		Front:___ Rear:___
4.55	Cupholder size adequate	Operation		Test with bottle
4.56	Door pockets/storage bins intact	Visual		All 4 doors
4.57	Seatback pockets (if equipped)	Visual		
4.58	Coat hooks present and functional	Visual/Operation		
4.59	Sun visor - both sides working	Operation		Flip and slide
4.60	Vanity mirrors present (if equipped)	Visual		
4.61	Vanity mirror lights working (if equipped)	Operation		
4.62	Grab handles present at all positions	Visual		Usually above doors
4.63	Grab handles firmly attached	Touch		Pull to test

4E: Floor & Carpeting

#	Checkpoint	Method	Rating	Remarks
4.64	Floor carpeting clean, no stains	Visual		
4.65	Carpeting properly fitted, no loose areas	Visual/Touch		
4.66	Floor mats present (if ordered/included)	Visual		Front:___ Rear:___
4.67	Floor mats properly fitted	Visual		Check driver side clips

#	Checkpoint	Method	Rating	Remarks
4.68	No abnormal smell from carpet/floor	Smell		Musty/chemical odor?
4.69	Pedal rubbers in good condition	Visual		Accelerator, Brake, Clutch
4.70	Dead pedal present (left footrest)	Visual		If equipped
4.71	Lift carpet to check for water leaks (if possible)	Visual/Touch		Ask dealer permission

4F: Doors & Windows (Interior)

#	Checkpoint	Method	Rating	Remarks
4.72	Interior door handles working smoothly	Operation		All 4 doors
4.73	Door panel upholstery perfect condition	Visual		
4.74	Door panel storage pockets clean	Visual		
4.75	Door speakers visible and undamaged	Visual		
4.76	Window switches - all working	Operation		All 4 windows
4.77	Driver window auto up/down working (if equipped)	Operation		One-touch function
4.78	Window anti-pinch safety working (if equipped)	Operation		Test with object
4.79	Child lock working on rear doors	Operation		Engage/disengage
4.80	Central locking - all doors lock/unlock together	Operation		From driver switch
4.81	Power door locks from each door (if equipped)	Operation		
4.82	Auto door lock on drive (if equipped)	Operation		Locks when moving
4.83	Auto door unlock on park (if equipped)	Operation		

4G: Roof & Lighting

#	Checkpoint	Method	Rating	Remarks
4.84	Roof lining clean, no stains	Visual		
4.85	Roof lining properly fitted, no sagging	Visual		
4.86	Dome light/cabin light working	Operation		On/off/door mode
4.87	Map lights/reading lights working (if equipped)	Operation		Front + rear
4.88	Ambient lighting working (if equipped)	Operation		Color changing
4.89	Foot well lighting working (if equipped)	Operation		
4.90	Door approach lighting working (if equipped)	Operation		Lights when door opens

4H: Rear Cabin & Boot

#	Checkpoint	Method	Rating	Remarks
4.91	Rear AC vents working (if equipped)	Operation		Feel airflow
4.92	Rear AC controls working (if equipped)	Operation		Temperature/fan

#	Checkpoint	Method	Rating	Remarks
4.93	Rear power outlets/USB ports working (if equipped)	Operation		Test with charger
4.94	Rear window defogger working	Operation		
4.95	Rear center armrest functions (if equipped)	Operation		Folds down
4.96	Rear armrest cupholders (if equipped)	Visual		
4.97	Boot space clean, no damage	Visual		
4.98	Boot carpet/liner properly fitted	Visual		
4.99	Boot light working	Operation		Comes on when opened
4.100	Boot release - interior button working	Operation		
4.101	Boot release - remote key working	Operation		
4.102	Boot release - exterior button working (if equipped)	Operation		
4.103	Parcel tray present (if applicable)	Visual		Sedan/hatchback
4.104	Parcel tray properly fitted	Visual		No rattles
4.105	Rear seats fold for extra space (if applicable)	Operation		Test mechanism

SECTION 5: ELECTRICAL & ELECTRONICS

Critical for modern vehicles - test everything

5A: Battery & Charging

#	Checkpoint	Method	Rating	Remarks
5.1	Battery manufacture date within last 3 months	Visual		Check sticker on battery
5.2	Battery terminals clean, tight, no corrosion	Visual		
5.3	Battery cables properly connected	Visual		Positive (red), Negative (black)
5.4	Battery hold-down bracket secure	Visual/Touch		No movement
5.5	Battery voltage 12.4-12.8V with engine off (use meter/OBD)	Measurement		___V
5.6	Charging voltage 13.8-14.4V with engine running	Measurement		___V
5.7	Battery warning light goes off after engine start	Operation		Critical check
5.8	Alternator charging properly (no whining noise)	Hearing		

5B: Infotainment System

#	Checkpoint	Method	Rating	Remarks
---	------------	--------	--------	---------

#	Checkpoint	Method	Rating	Remarks
5.9	Touchscreen size as per variant specification	Visual		Size: __ inches
5.10	Touchscreen responsiveness - no lag	Operation		Touch multiple areas
5.11	Screen brightness adequate in sunlight	Visual		Test in bright light
5.12	Screen clarity - no dead pixels or lines	Visual		White/black screen test
5.13	Protective film removed (if applicable)	Visual		Peel off if present
5.14	System boots up within 30 seconds	Operation		Time from ignition
5.15	System language set correctly	Operation		Change if needed
5.16	Date and time correct	Operation		Set if needed
5.17	Radio/FM tuner working	Operation		Scan stations
5.18	Radio presets saving	Operation		Save + recall
5.19	Radio sound quality good	Hearing		No distortion
5.20	All speakers working	Hearing		Use balance/fader settings
5.21	Speaker count matches variant	Hearing/Visual		Count: __ speakers
5.22	USB port working - plays music	Operation		Test with USB drive
5.23	USB ports charge phone (if equipped)	Operation		Test with cable
5.24	AUX input working (if equipped)	Operation		Test with cable
5.25	Bluetooth pairing working	Operation		Pair phone
5.26	Bluetooth audio streaming working	Operation		Play music from phone
5.27	Bluetooth call quality clear	Operation		Make test call
5.28	Android Auto connection working (if equipped)	Operation		With compatible phone
5.29	Apple CarPlay connection working (if equipped)	Operation		With compatible phone
5.30	Wireless Android Auto/CarPlay (if equipped)	Operation		
5.31	Voice commands working (if equipped)	Operation		Test few commands
5.32	Navigation system working (if equipped)	Operation		Set destination
5.33	Navigation GPS location accurate	Operation		Within 10 meters
5.34	Steering-mounted audio controls working	Operation		Volume, track, mode

5C: Climate Control

#	Checkpoint	Method	Rating	Remarks
5.35	AC compressor engages (RPM increases slightly)	Operation/Hearing		
5.36	AC cooling effective within 2-3 minutes	Touch/Feel		Measure if possible
5.37	AC vents - all opening/closing smoothly	Operation		All dashboard vents

#	Checkpoint	Method	Rating	Remarks
5.38	AC direction control working for all vents	Operation		Up/down/left/right
5.39	AC fan speed - all levels working	Operation		1, 2, 3, 4, Auto
5.40	AC temperature control working	Operation		Hot to cold adjustment
5.41	AC mode selection working	Operation		Face, feet, defrost
5.42	AC recirculation button working	Operation		Light indicator
5.43	Rear AC controls independent (if equipped)	Operation		
5.44	Rear AC cooling adequate (if equipped)	Feel		
5.45	AC filter clean, no bad odor from vents	Smell		Musty smell?
5.46	Heater working (test in cool morning if possible)	Operation		Hot air from vents
5.47	Rear defogger working	Operation		Indicator light on
5.48	Front defogger working	Operation		
5.49	Auto climate control working (if equipped)	Operation		Set temp + observe

5D: Wipers & Washers

#	Checkpoint	Method	Rating	Remarks
5.50	Front wiper blades - rubber in good condition	Visual/Touch		No cracks/hardness
5.51	Front wipers - all speeds working	Operation		Intermittent, low, high
5.52	Front wipers - return to park position	Operation		
5.53	Rain-sensing wipers working (if equipped)	Operation		Pour water on windshield
5.54	Rear wiper blade condition good (if equipped)	Visual/Touch		
5.55	Rear wiper working	Operation		
5.56	Windshield washer fluid level adequate	Visual		Check reservoir
5.57	Windshield washer spray working	Operation		Both jets spraying
5.58	Windshield washer spray pattern correct	Visual		Hits center of glass
5.59	Rear washer working (if equipped)	Operation		
5.60	Headlight washers working (if equipped)	Operation		High-end vehicles

5E: Power Accessories

#	Checkpoint	Method	Rating	Remarks
5.61	12V power outlets working	Operation		Test with phone charger
5.62	USB charging ports working - all positions	Operation		Front + rear
5.63	USB-C ports working (if equipped)	Operation		Fast charging

#	Checkpoint	Method	Rating	Remarks
5.64	Wireless phone charger working (if equipped)	Operation		Place compatible phone
5.65	Wireless charger cooling fan audible	Hearing		Slight fan noise OK
5.66	Cooled glove box working (if equipped)	Operation		Feel cold air
5.67	Powered tailgate working (if equipped)	Operation		Open/close button
5.68	Powered tailgate height adjustment (if equipped)	Operation		Program height
5.69	Kick sensor for tailgate (if equipped)	Operation		Wave foot under

SECTION 6: ADVANCED FEATURES & SAFETY SYSTEMS

If equipped - variant specific

6A: Camera Systems

#	Checkpoint	Method	Rating	Remarks
6.1	Reverse camera activates in reverse gear	Operation		Image on screen
6.2	Reverse camera image clear, no distortion	Visual		Day and evening
6.3	Reverse camera guidelines appearing	Visual		Dynamic/static lines
6.4	360-degree camera working (if equipped)	Operation		All 4 views
6.5	360 camera stitching quality good	Visual		No major distortion
6.6	Front camera clear (if equipped)	Visual		
6.7	Blind spot camera working (if equipped)	Operation		Turn indicators
6.8	Dashcam recording (if equipped)	Operation		Check memory card

6B: Parking Sensors

#	Checkpoint	Method	Rating	Remarks
6.9	Rear parking sensors - number matches variant	Visual/Operation		Usually 4 sensors
6.10	Rear parking sensors beeping when approaching object	Operation/Hearing		Distance-based beeps
6.11	Front parking sensors working (if equipped)	Operation		
6.12	Parking sensor volume adequate	Hearing		Not too loud/soft
6.13	Parking sensor display on screen (if equipped)	Visual		Distance shown

6C: ADAS (Advanced Driver Assistance Systems)

#	Checkpoint	Method	Rating	Remarks
---	------------	--------	--------	---------

#	Checkpoint	Method	Rating	Remarks
6.14	Adaptive cruise control working (if equipped)	Operation		Test during drive
6.15	Lane keep assist working (if equipped)	Operation		Steering correction
6.16	Lane departure warning (if equipped)	Operation		Visual/audio alert
6.17	Blind spot monitoring (if equipped)	Operation		Mirror/A-pillar light
6.18	Forward collision warning (if equipped)	Operation		Alert when close
6.19	Automatic emergency braking (if equipped)	Operation		Cannot fully test
6.20	Traffic sign recognition (if equipped)	Operation		Shows speed limits
6.21	Driver drowsiness detection (if equipped)	Operation		Coffee cup icon
6.22	High beam assist working (if equipped)	Operation		Auto dim/bright
6.23	Hill hold assist working	Operation		Test on slope
6.24	Hill descent control (if equipped)	Operation		For SUVs
6.25	Auto park assist (if equipped)	Operation		Parallel/perpendicular

6D: Keyless & Remote Features

#	Checkpoint	Method	Rating	Remarks
6.26	Remote key lock/unlock working	Operation		From 10m distance
6.27	Remote key boot release working	Operation		
6.28	Remote key panic alarm working	Operation		Test briefly
6.29	Keyless entry - door handles sensing (if equipped)	Operation		Touch to unlock
6.30	Push button start working (if equipped)	Operation		Brake + press
6.31	Key fob battery level adequate	Visual		Check indicator
6.32	Spare key working - all functions	Operation		Must test!
6.33	Connected car app pairing (if equipped)	Operation		Download + test
6.34	Remote AC start from app (if equipped)	Operation		
6.35	Vehicle tracking on app (if equipped)	Visual		Location shown
6.36	Geo-fence alerts (if equipped)	Operation		Set boundary
6.37	Remote door lock from app (if equipped)	Operation		

SECTION 7: ENGINE & MECHANICAL SYSTEMS

7A: Engine Bay Inspection

#	Checkpoint	Method	Rating	Remarks
7.1	Engine bay clean, no excessive dust	Visual		Light dust OK
7.2	Engine oil level between min-max marks	Visual		Check dipstick
7.3	Engine oil color golden/amber (new oil)	Visual		Not black

#	Checkpoint	Method	Rating	Remarks
7.4	Engine oil cap properly closed	Visual/Touch		Twist to verify
7.5	Coolant level between min-max marks	Visual		Reservoir check
7.6	Coolant color correct (usually green/orange/pink)	Visual		Not rusty
7.7	Coolant cap properly closed	Visual/Touch		
7.8	Brake fluid level between min-max	Visual		DOT 3/4 fluid
7.9	Brake fluid color clear/light yellow	Visual		Not dark
7.10	Power steering fluid level adequate (if hydraulic)	Visual		Many cars now electric
7.11	Windshield washer fluid topped up	Visual		Fill if low
7.12	No visible fluid leaks anywhere	Visual		Check around engine
7.13	No oil seepage from gaskets	Visual		Clean means no leaks
7.14	Battery terminals clean and tight	Visual		Already checked
7.15	Radiator hoses firm, no cracks	Visual/Touch		Squeeze gently
7.16	AC compressor belt condition good	Visual		No cracks/fraying
7.17	Alternator belt condition good	Visual		
7.18	Air filter housing properly closed	Visual		
7.19	No loose wires or hanging connectors	Visual		
7.20	Engine mounts appear intact	Visual		No torn rubber visible

7B: Engine Performance

#	Checkpoint	Method	Rating	Remarks
7.21	Engine starts immediately without hesitation	Operation		1-2 crank rotations
7.22	Engine idle smooth - no shaking/vibration	Operation/Feel		Sit in car, engine on
7.23	Engine RPM stable at idle	Visual		600-800 RPM typical
7.24	No unusual engine noises (knocking, ticking, whining)	Hearing		Listen carefully
7.25	No excessive engine vibration at idle	Feel		Place hand on steering
7.26	Throttle response immediate	Operation		Press accelerator
7.27	Engine revs smoothly to redline (in neutral)	Operation		Rev slowly, listen
7.28	No smoke from exhaust	Visual		Check behind vehicle
7.29	Exhaust smell normal (not sweet/burning)	Smell		
7.30	Engine temperature gauge reaches normal (after 10min)	Visual		Middle position

7C: Transmission & Clutch

FOR MANUAL TRANSMISSION:

#	Checkpoint	Method	Rating	Remarks
7.31	Clutch pedal feel firm, progressive	Feel		Not spongy
7.32	Clutch engagement point in upper half of travel	Operation		Not at floor
7.33	Clutch pedal free play 1-2cm	Measurement		Normal spec
7.34	No noise when pressing clutch	Hearing		Smooth operation
7.35	Gearshift moves smoothly through all gears	Operation		1-2-3-4-5-R (6 if applicable)
7.36	No grinding when changing gears	Hearing		Smooth engagement
7.37	Reverse gear engages smoothly	Operation		May have slight resistance
7.38	Gear positions clearly defined (no vagueness)	Feel		Positive slots
7.39	Gear knob properly fitted	Visual/Touch		

FOR AUTOMATIC TRANSMISSION (AT/AMT/CVT/DCT):

#	Checkpoint	Method	Rating	Remarks
7.40	Gear selector moves through all positions	Operation		P-R-N-D-S/M
7.41	Transmission shifts smoothly during drive	Operation		Test drive required
7.42	No jerks when changing gears	Feel		Smooth transitions
7.43	No delay when engaging D or R	Operation		Immediate response
7.44	Tiptronic/manual mode working (if equipped)	Operation		+/- paddle/lever
7.45	Sport/Eco modes working (if equipped)	Operation		Feel difference
7.46	Transmission won't start unless in P/N	Operation		Safety feature
7.47	Cannot remove key unless in P (if applicable)	Operation		Shift lock

7D: Braking System

#	Checkpoint	Method	Rating	Remarks
7.48	Brake pedal feel firm when pressed	Feel		Not spongy/soft
7.49	Brake pedal free play minimal	Feel		1-2cm max
7.50	Brakes bite progressively	Operation		Linear response
7.51	No noise from brakes (squeaking/grinding)	Hearing		During test drive
7.52	Vehicle stops straight, no pulling	Operation		Test drive
7.53	Parking brake/handbrake holds vehicle on slope	Operation		Test on incline
7.54	Electronic parking brake working (if equipped)	Operation		Auto-hold feature
7.55	ABS working (cannot lock wheels)	Operation		Hard brake test
7.56	ABS warning light goes off after start	Visual		Must check
7.57	Brake assist working (if equipped)	Operation		Hard to test fully

#	Checkpoint	Method	Rating	Remarks
7.58	Brake pads thickness adequate (visual if possible)	Visual		Through wheel spokes

7E: Steering System

#	Checkpoint	Method	Rating	Remarks
7.59	Steering wheel centered when driving straight	Visual/Feel		Must be straight
7.60	Steering freeplay minimal	Operation		1-2cm max
7.61	Power steering working smoothly	Operation		Easy to turn
7.62	No unusual noise from steering	Hearing		No grinding/whining
7.63	Steering returns to center after turn	Operation		Self-centering
7.64	Electric steering weight adjustable (if equipped)	Operation		Light/Normal/Sport modes
7.65	Steering vibration-free at all speeds	Feel		During test drive

7F: Suspension & Handling

#	Checkpoint	Method	Rating	Remarks
7.66	Suspension bounce test - rebounds once	Operation		Press down each corner
7.67	No unusual noise from suspension over bumps	Hearing		Test drive
7.68	Ride quality comfortable	Feel		Subjective assessment
7.69	No rattles from chassis	Hearing		Speed bumps test
7.70	Vehicle stable at highway speeds (if test allowed)	Feel		80-100 km/h

SECTION 8: FUEL SYSTEM CHECKS

Fuel-type specific inspection

8A: Petrol/Diesel Vehicles

#	Checkpoint	Method	Rating	Remarks
8.1	Fuel type matches variant purchased	Visual		Petrol/Diesel label
8.2	Fuel tank capacity matches specification	Visual		Check manual
8.3	Fuel gauge shows correct level	Visual		Should be full/3/4
8.4	Fuel filler neck clean	Visual		No debris
8.5	Fuel cap seals properly, no damage	Operation		Twist and check
8.6	No fuel smell in cabin	Smell		Indicates leak
8.7	No fuel leaks visible under vehicle	Visual		

8B: CNG Vehicles (Additional Checks)

#	Checkpoint	Method	Rating	Remarks
8.8	CNG cylinder installed properly in boot	Visual		Takes boot space
8.9	CNG cylinder manufacture date within 6 months	Visual		Check label on cylinder
8.10	CNG cylinder hydro-test date valid (15 years from mfg)	Visual		Check stamp
8.11	CNG cylinder weight/capacity matches specification	Visual		60L/65L/80L typical
8.12	CNG kit brand matches approved list	Visual		Lovato/Tomasetto/BRC
8.13	CNG regulator/reducer properly installed	Visual		In engine bay
8.14	CNG pressure gauge working on dashboard	Operation		Shows bar/kg pressure
8.15	CNG-Petrol selector switch working	Operation		Manual/automatic switch
8.16	Vehicle starts on CNG mode (if auto switch)	Operation		Or petrol then switches
8.17	CNG fuel line properly routed and secured	Visual		No hanging wires
8.18	CNG pipes have no leaks (soap water test)	Operation		Dealer should do
8.19	No CNG smell from engine bay or boot	Smell		Very important safety check
8.20	CNG safety valve present on cylinder	Visual		Pressure relief device
8.21	CNG filling valve accessible	Visual		Usually rear bumper
8.22	CNG certification/bi-fuel certificate present	Visual		Legal requirement

8C: Electric Vehicles (Additional Checks)

#	Checkpoint	Method	Rating	Remarks
8.23	Battery State of Charge (SOC) level	Visual		Should be 80-100%
8.24	Battery health percentage shown	Visual		Should be 100% for new
8.25	Estimated range shown matches specification	Visual		ARAI/EPA range
8.26	Charging port door opens/closes smoothly	Operation		
8.27	Charging port pins clean, no corrosion	Visual		AC + DC ports
8.28	Charging cable(s) provided	Visual		Type 2 AC + CCS2 DC
8.29	Portable charger (EVSE) provided	Visual		3-pin/16A charger
8.30	Charging cable storage bag present	Visual		
8.31	Home charging wallbox installed (if ordered)	Visual		Separate item

#	Checkpoint	Method	Rating	Remarks
8.32	Test AC charging - vehicle accepts charge	Operation		Plug in and verify
8.33	DC fast charging port accessible (if equipped)	Visual		CCS2 standard
8.34	Battery thermal management working	Operation		Cooling/heating system
8.35	Regenerative braking working	Operation		Lift throttle, feel regen
8.36	Regen braking levels adjustable (if equipped)	Operation		Low/Medium/High
8.37	One-pedal driving mode working (if equipped)	Operation		Strong regen
8.38	EV drive modes working	Operation		Eco/Normal/Sport/Custom
8.39	Scheduled charging working (if equipped)	Operation		Set time in menu
8.40	Charge limit setting working	Operation		Set to 80% for test
8.41	Battery warranty terms understood	Visual		8 years/1.6L km typical
8.42	No high-voltage warning lights on dashboard	Visual		"Turtle" mode icon
8.43	12V auxiliary battery healthy	Visual/Measurement		EV has 2 batteries
8.44	V2L (Vehicle to Load) working (if equipped)	Operation		Power external devices

8D: Hybrid Vehicles (Additional Checks)

#	Checkpoint	Method	Rating	Remarks
8.45	Hybrid system type understood	Visual		Full/Mild/Plug-in
8.46	Battery SOC indicator working	Visual		Separate from fuel
8.47	EV mode working (for PHEV/Strong Hybrid)	Operation		Drive on electric only
8.48	Engine starts/stops smoothly (auto start-stop)	Operation		Should be seamless
8.49	Regenerative braking working	Operation		Charges battery
8.50	Energy flow display working	Visual		Shows power routing
8.51	Hybrid battery cooling system working	Operation		Fan audible when hot
8.52	Charging port functional (for PHEV)	Operation		Like EV checks above

SECTION 9: OBD2 DIAGNOSTICS SCAN

Highly recommended for peace of mind

9A: OBD2 Connection

#	Checkpoint	Method	Rating	Remarks
9.1	Locate OBD2 port (usually below dashboard driver side)	Visual		
9.2	Connect OBD2 Bluetooth scanner	Operation		ELM327 or similar
9.3	Pair scanner with smartphone app	Operation		Torque/Car Scanner app
9.4	Successfully connect to vehicle ECU	Operation		

9B: OBD2 Data Reading

#	Checkpoint	Method	Rating	Remarks
9.5	Read Diagnostic Trouble Codes (DTCs)	Operation		Should be ZERO codes
9.6	Check engine (P codes) - none present	Visual		P0XXX codes
9.7	Transmission codes (P codes) - none present	Visual		
9.8	Body control codes (B codes) - none present	Visual		B0XXX codes
9.9	Chassis codes (C codes) - none present	Visual		C0XXX codes
9.10	Network codes (U codes) - none present	Visual		U0XXX codes
9.11	Check for Pending Codes (may appear soon)	Visual		Should be ZERO
9.12	Check for Permanent Codes	Visual		Should be ZERO
9.13	Check Freeze Frame Data (error conditions)	Visual		Should be blank
9.14	Verify VIN matches vehicle documents	Visual		17-character code
9.15	Check odometer reading matches dashboard	Visual		Confirms no tampering

9C: Live Data Monitoring

#	Checkpoint	Method	Rating	Remarks
9.16	Engine RPM reading accurate	Visual		Match with dashboard
9.17	Engine coolant temperature normal range	Visual		80-95°C when warm
9.18	Intake air temperature reasonable	Visual		Ambient + 10-20°C
9.19	Throttle position sensor working	Visual		0% idle, 100% full
9.20	Mass air flow (MAF) sensor reading	Visual		2-7 g/s at idle
9.21	Oxygen sensor readings (O2)	Visual		Switching 0.1-0.9V
9.22	Fuel system status	Visual		Closed loop normal
9.23	Calculated engine load	Visual		15-30% at idle
9.24	Battery voltage	Visual		12.4-12.8V off, 13.8-14.4V on
9.25	Vehicle speed matches GPS (during test drive)	Visual		Should match closely

9D: Readiness Monitors

#	Checkpoint	Method	Rating	Remarks
9.26	OBD Readiness Status	Visual		All monitors "Ready"
9.27	Catalyst monitor ready	Visual		May take 50-100km for new car
9.28	Evaporative system ready	Visual		
9.29	Oxygen sensor ready	Visual		
9.30	EGR system ready (if applicable)	Visual		

If **ANY** error codes present: Note them down, ask dealer to clear and explain. Some codes OK for brand new car (catalyst not ready), but engine/transmission errors are MAJOR issues.

SECTION 10: TEST DRIVE EVALUATION

CRITICAL - Never skip this section

10A: Pre-Drive Checks

#	Checkpoint	Method	Rating	Remarks
10.1	Adjust driver seat for comfort	Operation		Forward/back, height, recline
10.2	Adjust steering wheel position	Operation		Tilt and telescopic
10.3	Adjust all 3 mirrors properly	Operation		Interior + both ORVMs
10.4	Fasten seatbelt, verify reminder works	Operation		
10.5	Start engine smoothly	Operation		
10.6	Check all warning lights go off	Visual		Critical safety check
10.7	Plan route: straight road + curves + bumps + slope	Visual		Cover variety

10B: Low-Speed Maneuvering (Dealer Premises)

#	Checkpoint	Method	Rating	Remarks
10.8	Clutch bite point comfortable (manual)	Feel		
10.9	Transmission engages smoothly (automatic)	Feel		
10.10	Throttle response linear	Feel		Not jerky
10.11	Brakes bite progressively	Feel		Not grabby
10.12	Steering weight appropriate	Feel		Not too heavy/light
10.13	Turning circle reasonable	Operation		Full lock turns
10.14	Reverse camera/sensors working	Visual/Hearing		Already checked but reconfirm
10.15	No unusual noises at low speed	Hearing		Creaks, rattles

10C: City Driving (20-60 km/h)

#	Checkpoint	Method	Rating	Remarks
10.16	Acceleration smooth in all gears	Feel		No hesitation
10.17	Gear shifts smooth (manual)	Operation		All gears 1-5/6
10.18	Automatic transmission shifts smoothly	Feel		No jerks
10.19	No transmission whine or grinding	Hearing		Should be quiet
10.20	Engine pulls strongly without hesitation	Feel		Good power delivery
10.21	No engine vibration through steering/pedals	Feel		
10.22	Brakes stop vehicle straight	Operation		No pulling left/right
10.23	Brake pedal travel consistent	Feel		Not spongy
10.24	No brake noise during normal braking	Hearing		
10.25	Suspension absorbs bumps well	Feel		Not too harsh/soft
10.26	No suspension noise over bumps	Hearing		Clunks, thuds
10.27	Steering tracks straight on straight road	Feel		Release hands briefly
10.28	No steering vibration	Feel		Smooth rim

10D: Highway/Open Road (60-100 km/h) - If Allowed

#	Checkpoint	Method	Rating	Remarks
10.29	Engine pulls strongly at higher RPMs	Feel		Good power reserve
10.30	Transmission upshifts smoothly	Feel/Hearing		
10.31	Transmission kickdown works (automatic)	Operation		Downshifts when floor pedal
10.32	Vehicle stable at highway speeds	Feel		No wandering
10.33	No steering shimmy or vibration at speed	Feel		80-100 km/h critical
10.34	Wind noise acceptable	Hearing		Some noise normal
10.35	Road noise acceptable	Hearing		Depends on tyres
10.36	Engine noise acceptable at cruise	Hearing		Not too loud
10.37	High-speed braking stable	Operation		Emergency brake test
10.38	ABS activates on hard braking	Feel		Pedal pulsation

10E: Special Conditions

#	Checkpoint	Method	Rating	Remarks
10.39	Hill start assist working (if equipped)	Operation		Stop on slope, no rollback
10.40	Hill descent control working (if equipped)	Operation		SUVs with this feature
10.41	Speed breaker/pothole absorption	Feel		Harsh roads common in India
10.42	U-turn clearance adequate	Operation		Check ground clearance
10.43	AC cooling adequate during drive	Feel		Should be cold
10.44	No unusual smells during drive	Smell		Burning, clutch burning

10F: After Test Drive

#	Checkpoint	Method	Rating	Remarks
10.45	Engine temperature gauge normal	Visual		Center position
10.46	No warning lights appeared	Visual		Check dashboard
10.47	No new rattles or noises developed	Hearing		
10.48	Check for fluid leaks after drive	Visual		Look under vehicle
10.49	Overall driving experience satisfactory	Feel		Your gut feeling matters!

Test Drive Duration: Minimum 15-20 minutes to check all conditions.

SECTION 11: ACCESSORIES & ADD-ONS VERIFICATION

#	Checkpoint	Method	Rating	Remarks
11.1	All dealer-fitted accessories as per order	Visual		List:
11.2	Door visors fitted properly (if ordered)	Visual		No gaps
11.3	Mud flaps fitted (if ordered)	Visual		All 4 wheels
11.4	Body side molding (if ordered)	Visual		Aligned properly
11.5	Seat covers fitted properly (if ordered)	Visual		No wrinkles
11.6	Floor mats - full set present	Visual		Driver, passenger, rear
11.7	Boot mat/tray present (if ordered)	Visual		
11.8	Rear parking camera aftermarket (if added)	Operation		Test functionality
11.9	Aftermarket infotainment (if added)	Operation		All features working
11.10	Reverse sensors aftermarket (if added)	Operation		Beeping properly
11.11	Perfume/air freshener (if included)	Visual		Dealer freebies
11.12	First aid kit (if included)	Visual		Check contents
11.13	Fire extinguisher (mandatory for some states)	Visual		Check expiry date
11.14	Warning triangle/reflectors	Visual		Safety equipment
11.15	Toolkit complete in boot	Visual		Jack, spanner, etc.
11.16	Owner's manual and all booklets	Visual		Multiple languages
11.17	Warranty cards for accessories	Visual		Separate from vehicle

SECTION 12: FINAL VERIFICATION & HANDOVER

12A: Final Walkthrough

#	Checkpoint	Method Rating	Remarks
12.1	Vehicle completely clean inside and out	Visual	Ask for wash if needed
12.2	All protective stickers/covers removed	Visual	Infotainment, seats, floor
12.3	No scratches introduced during PDI	Visual	Compare with initial photos
12.4	Fuel tank filled to agreed level	Visual	Full tank or ___%
12.5	All agreed repairs/issues fixed	Visual	Recheck marked items

12B: Documentation Final Check

#	Checkpoint	Method Rating	Remarks
12.6	All documents present and signed	Visual	16-point doc list
12.7	Registration process explained by dealer	Hearing	Timeline: ___ days
12.8	Insurance process explained	Hearing	Active from: _____
12.9	First free service date scheduled	Visual	At: _____ km or ___ months
12.10	Service center location and contact saved	Visual	Phone: _____
12.11	Roadside assistance number saved	Visual	24/7 helpline
12.12	Extended warranty details understood (if opted)	Hearing	Terms clear

12C: Handover Protocol

#	Checkpoint	Method Rating	Remarks
12.13	Both keys received and tested	Operation	Primary + spare
12.14	Key fob battery type noted	Visual	CR2032 or similar
12.15	Vehicle features demonstration by dealer	Hearing	30-min walkthrough
12.16	Special features operation understood	Hearing	ADAS, drive modes, etc.
12.17	Emergency procedures explained	Hearing	Flat tyre, breakdown
12.18	Dealer contact person details noted	Visual	Name: _____ Ph: _____
12.19	Feedback form filled (if any)	Operation	Rate dealer experience
12.20	Delivery certificate signed by both parties	Operation	Get copy

12D: Photo Documentation

#	Checkpoint	Method Rating	Remarks
12.21	Take photos of full vehicle - all 4 sides	Visual	Timestamp important
12.22	Photo of odometer reading	Visual	_____ km at delivery
12.23	Photo of VIN plate	Visual	Dashboard + door pillar
12.24	Photo of engine bay	Visual	General condition
12.25	Photo of all 4 tyres with DOT date visible	Visual	Proof of manufacture date
12.26	Photo of spare tyre	Visual	
12.27	Photos of any minor issues noted	Visual	For future reference
12.28	Group photo with vehicle (optional)	Visual	Memorable moment!

SECTION 13: ISSUE SUMMARY & DEALER ACKNOWLEDGMENT

Issues Found During PDI

Issue #	Section Description	Severity	Dealer Action	Fixed?	Remarks
1		☐ Minor ☐ Major	☐ Fix now ☐ Fix later	☐ Yes ☐ No	
2		☐ Minor ☐ Major	☐ Fix now ☐ Fix later	☐ Yes ☐ No	
3		☐ Minor ☐ Major	☐ Fix now ☐ Fix later	☐ Yes ☐ No	
4		☐ Minor ☐ Major	☐ Fix now ☐ Fix later	☐ Yes ☐ No	
5		☐ Minor ☐ Major	☐ Fix now ☐ Fix later	☐ Yes ☐ No	

Total Issues Found: Minor: ____ | Major: ____

Decision:

- ☐ **ACCEPT DELIVERY** - All issues resolved or acceptable
- ☐ **POSTPONE DELIVERY** - Fix issues first, re-inspect on: _____
- ☐ **REJECT VEHICLE** - Major unresolved issues, request replacement unit

FINAL SIGN-OFF

Customer Declaration

I/We have thoroughly inspected the vehicle as per this comprehensive PDI checksheet. I/We understand that accepting delivery means I/We are satisfied with the vehicle's condition. Any issues noted above will be addressed as per dealer commitment.

Customer Name: _____

Customer Signature: _____ Date: _____

Customer Contact: _____

Dealer Representative Acknowledgment

I confirm that the customer has been given adequate time (minimum 90 minutes) to inspect the vehicle. All issues raised have been noted and will be addressed as committed.

Dealer Rep Name: _____

Dealer Rep Signature: _____ Date: _____

Dealership Name: _____

Dealership Stamp:

IMPORTANT REMINDERS - READ BEFORE STARTING PDI

Best Practices:

1. ☐ **Never rush** - Take minimum 90 minutes
2. ☐ **Daylight inspection** - 10 AM to 4 PM ideal
3. ☐ **Bring helpers** - 2-3 people catch more issues
4. ☐ **Document everything** - Photos are proof
5. ☐ **Test everything** - Don't assume anything works
6. ☐ **Ask questions** - Dealer should explain features
7. ☐ **Compare with brochure** - Verify all promised features
8. ☐ **Check manufacturing dates** - Tyres, battery, vehicle (VIN decode)
9. ☐ **OBD scan mandatory** - Reveals hidden issues
10. ☐ **Test drive non-negotiable** - 20+ minutes minimum

Red Flags - DO NOT Accept Delivery If:

- ☐ Any **MAJOR** issue remains unfixed
- ☐ Odometer reading over 200 km (excessive dealer use)
- ☐ Paint thickness meter shows repainting
- ☐ OBD2 scanner shows error codes
- ☐ Vehicle pulls to one side when driving straight
- ☐ Transmission grinding/jerking
- ☐ Engine warning lights stay on
- ☐ Airbag warning light stays on
- ☐ Documents don't match vehicle VIN/Engine number
- ☐ Tyres manufactured over 12 months ago
- ☐ Battery manufactured over 6 months ago
- ☐ Any safety system not working (ABS, airbags, seatbelts)

Your Rights as Customer:

1. You have the RIGHT to conduct thorough PDI - dealer cannot rush you
2. You have the RIGHT to reject delivery if major defects found
3. You have the RIGHT to postpone delivery until issues fixed
4. You have the RIGHT to request replacement vehicle if multiple issues
5. You have the RIGHT to third-party inspection before registration
6. You have the RIGHT to full refund if rejecting before registration

After Delivery:

- Keep this completed checksheet safely
- Keep all photos backed up
- Note first service date
- Join owner community groups
- Report any post-delivery issues within 48 hours
- Follow break-in period guidelines (first 1000-2000 km)

ANNEXURE: QUICK REFERENCE TABLES

A1: Normal Operating Values

Parameter	Normal Range	Method to Check
Engine Oil Level	Between MIN-MAX marks	Dipstick
Coolant Level	Between MIN-MAX marks	Reservoir
Battery Voltage (Off)	12.4 - 12.8V	Multimeter/OBD2
Battery Voltage (On)	13.8 - 14.4V	Multimeter/OBD2
Engine Idle RPM	600 - 900 RPM	Tachometer
Engine Coolant Temp	80 - 95°C	OBD2/Gauge
Tyre Pressure	As per door sticker	Pressure gauge
Tyre Tread Depth	7 - 8mm (new)	Tread gauge
Odometer Reading	Under 100 km ideal	Dashboard
Paint Thickness	100 - 180 microns	Paint meter

A2: Tyre Manufacturing Date Decoder

DOT Code Format: DOT XXXX WWYY

Example: DOT AX12 2024

- First 2 digits (**20**) = Week number (20th week = Mid-May)

- Last 2 digits (24) = Year (2024)
- This tyre was made in 20th week of 2024 (May 2024)

Acceptable Age: Within 6 months of delivery date (12 months maximum)

A3: Warning Lights Guide

Light Symbol	Name	Expected Behavior
☐ Engine	Check Engine	ON briefly on start, then OFF
☐ Battery	Battery/Charging	ON briefly on start, then OFF
☐ Oil Pressure	Oil Pressure Low	ON briefly on start, then OFF
☐ ABS	Anti-lock Braking	ON briefly on start, then OFF
☐ Airbag/SRS	Airbag System	ON briefly on start, then OFF
☐ TPMS	Tyre Pressure	ON briefly on start, then OFF
☐ Brake	Brake System	OFF (ON only if handbrake applied)
☐ ESP/Stability	Stability Control	ON briefly on start, then OFF
☐ Steering	Power Steering	ON briefly on start, then OFF
☐ Service	Service Due	May be ON if service due

If ANY red light stays ON after engine start = DO NOT accept delivery until fixed

A4: Fuel Types & Specifications

Fuel Type	Emission Std	Octane/Cetane	Additional Check
Petrol	BS6	RON 91+	E10 or E20 ethanol blend
Diesel	BS6	Cetane 51+	AdBlue tank (if SCR equipped)
CNG	NG	Methane 85%+	Bi-fuel certificate, cylinder test date
EV	-	-	Charging cables, battery warranty
Hybrid	BS6	Varies	Hybrid battery warranty, cooling

A5: Document Checklist Summary

#	Document	Must Have?	Where to Check
1	Invoice	☐ Mandatory	Name, amount, VIN match
2	RC Book/Temp Registration	☐ Mandatory	Name, VIN, engine no. match
3	Insurance Policy	☐ Mandatory	Valid from delivery date
4	PUC Certificate	☐ Mandatory	Valid 1 year
5	Warranty Booklet	☐ Mandatory	Dealer stamp + sign
6	Owner's Manual	☐ Mandatory	Correct language
7	Service Booklet	☐ Mandatory	Record maintenance
8	Payment Receipts	☐ Mandatory	All amounts
9	Duplicate Keys	☐ Mandatory	Test both keys
10	Battery Warranty	☒ Recommended	Separate card
11	Tyre Warranty	☒ Recommended	Separate card
12	Extended Warranty	☒ If purchased	Terms clear
13	Roadside Assistance	☒ Recommended	Contact number

#	Document	Must Have?	Where to Check
14	FASTag Receipt	☒ If applicable	Activation status
15	CNG Certificate	☒ CNG vehicles	Legal requirement
16	Loan Documents	☒ If financed	Terms + foreclosure

ABOUT THIS CHECKSHEET

Version: 1.0 | **October 2024** **Location:** Gujarat, India **Applicability:** Universal - All vehicle types

Based on best practices from:

- Zekardo (3700+ checkpoints system)
- CarVaidya (360° AI-enabled inspection)
- Cars24 (Professional PDI standards)
- PDI Boss (3500+ vehicle checkpoints)
- Team-BHP (Community-driven excellence)
- CarCID (300+ examination points)

Expert Profile: 15 years automotive inspection experience, certified vehicle inspector, Gujarat-based operations

Usage Rights: Free to use for personal vehicle PDI. Not for commercial redistribution without permission.

Feedback: This is a living document. Suggestions for improvement welcome.

CONCLUSION

Congratulations on your new vehicle purchase! This comprehensive PDI checksheet ensures that you receive your vehicle in perfect condition. Remember:

☐ Your vigilance today prevents problems tomorrow ☐ A thorough PDI takes time - invest it wisely ☐
**Documentation is your proof - maintain it carefully ☐ When in doubt, don't accept - demand resolution ☐ Your
safety and satisfaction are paramount**

Drive Safe, Drive Happy! ☐ ☐

Emergency Contacts to Save:

- Dealer Service Center: _____
- Roadside Assistance: _____
- Insurance Company: _____
- RTO Office: _____
- Service Booking App: _____

First Service: Book at _____ km or _____ months (whichever earlier)

Next Steps After Delivery:

1. ☐ Install FASTag (if not done)
2. ☐ Download manufacturer's app
3. ☐ Join owner community groups
4. ☐ Save all contacts
5. ☐ Plan first service
6. ☐ Read owner's manual fully
7. ☐ Enjoy your new car! ☐

END OF PROFESSIONAL PDI GUIDELINE & CHECKSHEET

Safe motoring ahead! - Your 15-Year Industry Expert